SYSTEM NAME	**PLANT, VEHICLE & EQUIPMENT** PROCEDURE
SYSTEM NUMBER	RNSWP007
PURPOSE & SCOPE	To ensure that all plant & equipment is effectively purchased, used, maintained and disposed of in a safe manner.
CONNECTING DOCUMENTS	RNSWF018 Plant & Equipment Register

TASK	STEPS	FREQUENCY	POSITION
Incorporating SAFE Risk Management	All Plant & Equipment risks must be either eliminated or reduced following the company's SAFE Risk Management Program. That is: 1. **S**pot the hazard 2. **A**ssess the Risks 3. **F**ix the problem 4. **E**valuate the effectiveness of the controls put in place	All Equipment	HSEQ Team
Plant, Vehicle & Equipment Register	All Plant & Equipment must be recorded in the **RNSWF018 Plant & Equipment Register.** All fields must be filled out in the register. The register is reviewed annually.	Before any Plant or Equipment is used the first time	HSEQ Team
Purchasing and hiring plant	Before purchasing or hiring any plant or equipment, follow the two steps below: 1. Discuss needs and obtain information about the plant or equipment from the supplier/hirer 2. Determine all hazards & risks associated with the plant or equipment and the control measures that will be necessary to make it safe NOTE: Particular care should be taken when purchasing second-hand plant or equipment.	Before Purchasing and hiring plant	HSEQ Team
Registering Plant or Equipment	All vehicles must be registered as per state requirements. Certain plant designs and items of plant to be registered (registrable plant). You must not allow the use of any registrable plant in the workplace if it has not been registered.	Before the Plant or Equipment enters the site	HSEQ Team

Installation and commissioning of plant	All plant & equipment must be installed, positioned in the workplace and commissioned by a competent person and in accordance the Code of Practice "Managing risks of plant in the Workplace" section 3.2.	During Installation and commissioning of plant	Installer
Developing a Safe Operating Instruction (SOP)	All plant & equipment must have a specific SOP developed. The SOP is to be reviewed annually or when there are any changes to the plant or equipment. A list of all completed **Safe Operating Procedures (SOP)** are listed in Smartsheet.	Before any plant or equipment is used the first time	-
Instruction, training and supervision	All workers and other persons who are to use the plant or equipment must be provided with information, training, instruction or supervision that is necessary to protect them from risks arising from the use of the plant. All persons using the plant or equipment must be trained in the applicable SOP and also observation completed and signed off through Smartsheet. All persons using the plant or equipment must be monitored until competent in its safe use.	Before person uses any plant or equipment the first time and annually thereafter	Supervisor
Using plant in the workplace	Workers who operate plant or equipment should be competent, or suitably supervised during training, so that they do not put themselves or others at risk. All operating manuals and instructional material provided by the manufacturer must be kept. You should also consider and address the risks that may arise from: • Operator fitness for work, for example, fatigue • Carrying out routine or repetitive tasks • Local conditions and working procedures.	During the use of the plant or equipment	Supervisor
Drivers & Operator Licensing	Certain types of plant, such as industrial lift trucks and some types of cranes, require the operator to have a high-risk work licence before they can operate the plant. Ensure that all operators are licenced before using this plant or equipment. Refer to the **License and Competency Table** as listed in this procedure. All operators that operate any vehicles on any roads must be licenced as required by state legal requirements. Refer to NSW requirements here https://www.nsw.gov.au/driving-boating-and-transport/driver-and-rider-licences/licence-classes-and-conditions/classes Before commencing work, all drivers of any	-	HSEQ Team

	company owned vehicles, will be required to provide a copy of your valid Driver's licence along with an RMS printout of demerit points against your licence. You must hold the appropriate licence for the vehicle you will be operating. You must hold a valid driver's licence with you whilst operating any vehicle at all times. It is the responsibility of the driver to ensure their licence is renewed as required prior to it expiring. A copy of the latest driver's licence will be requested initially and also at periodic intervals of each year.		
Making changes	If you intend to use plant in a different way, purpose or make any changes that it was not designed for, you must ensure that the risks associated with the new use are assessed by a competent person using the SAFE Methodology. Prior to making any alterations to plant or equipment, consult with the designer and manufacturer to ensure all relevant safety issues have been considered. NOTE: Any alterations that are made to the plant will result in the company assuming the obligations of a designer or manufacturer.	Before any changes	HSEQ Team
Prestarts of plant	Prestart Checklists using Smartsheet is to be completed daily before the machine is used.	As per manufacturers instruction or annually	HSEQ Team
Maintenance, repair and cleaning of plant	Plant must be maintained and repaired according to the manufacturer's specifications or, in the absence of such specifications, in accordance with a competent person's recommendations. Where applicable, plant & equipment should be isolated before maintenance or cleaning commences	-	Plant Supervisor
Storing plant	Plant that is not in use must be stored so that it does not create a risk to workers or other people in the workplace. Refer to Managing risks of plant in the workplace Code of Practice section 3.8.	-	Plant Supervisor
Decommissioning, dismantling and disposing of plant	Any hazards inherent in the process of decommissioning and dismantling the plant (for example, exposure to hazardous substances) should be identified. The plant should be dismantled in accordance with the designer's and manufacturer's instructions.	Prior to Decommissioning, dismantling and disposing of plant	Plant supervisor

Record Keeping	Records associated with plant registration, manuals inspections, service reports etc. must be kept, stored and disposed of in accordance with the index of records.	As per the Index of Records	HSEQ Team
Consultation	When deciding how to implement the appropriate plant or equipment procedures, workers must be consulted who will be directly affected by this decision. Their experience will help you choose appropriate control measures, and their involvement will increase the level of acceptance of any changes that may be needed to the way they do their job.	Every time	HSEQ Team

Licence & Competence Requirements

CLASSIFICATION	DESCRIPTION	LICENSE/CERTIFICATE/COMPETENCY
Asbestos	Remove non-friable asbestos	CPCCDE3014A
	Remove friable asbestos	CPCCDE3015A
	Supervise asbestos removal	CPCCBC4051A
	Workers carrying out asbestos-related work (non-removal	Trained in identifying asbestos and safe handling
Air quality monitoring	Carry out air quality monitoring	Qualified Hygienist
Concrete Pump	Concrete placing booms	PB
Cranes	Bridge and gantry cranes	CB
	Derrick crane	CD
	Non slewing mobile cranes greater than three tonnes capacity	CN
	Portal boom crane	CP
	Slewing mobile cranes	C2, C6, C1, C0
	Vehicle loading crane	CV
Dogging	Dogging	DG
EWP	Boom-type elevating work platform	WP
	Scissor Lift	WP or Yellow Card
Electrical	Electrical work	Electrical Contractors License
Fall arrest/fall restraint – use of	Using falling arrest or fall restraint equipment	WP, working at Heights training
Fall prevention system	Installation of fall preventionsystem	Training in the installation procedure by manufacturer
First Aid	Occupational First aid	Level 3 OFA/L3
	Senior First aid	Level 2 SFA
Forklift	Forklift truck	LF
	Order-picking forklift truck	LO
Formwork	Formwork Inspection	Engineer
	Installation of formwork systems	Evidence of training in formwork system
Gas fitting	Gas fitting work	Contractor's license, supervisors' certificate, tradesman
Hoist	Materials platform hoist	HM
	Personnel and material hoists	HP
Installation of fall arrest attachment points	Install anchor points for fall arrest. fall restraint	Trained in manufacturers system, rigger
Load Shifting	Front end loader	LL or a certificate of competency issued by a registered training organisation
	Front end loader/backhoe	LB or a certificate of competency issued bya registered training organisation
	Front end loader of the skid steertype	LS or a certificate of competency issued bya registered training organisation
	Excavator.	LE or a certificate of competency issued by a registered training organisation
	Telescopic Handler < 3 tonne	Certificate of competency issued by a registered training organisation
	Telescopic Handler > 3 tonne	CN
Plumbing		Contractor's licence, supervisors' certificate, tradesman
Rigging	Basic rigging	RB

CLASSIFICATION	DESCRIPTION	LICENSE/CERTIFICATE/COMPETENCY
	Intermediate rigging	RI
Refrigeration/air conditioning work	Air-conditioning and/or refrigerationwork	Supervisor License or Contractors licensefor air-conditioning or refrigeration work
Scaffolding	Advanced rigging	RA
	Basic scaffolding	SB
	Intermediate scaffolding	SI
	Advanced scaffolding	SA
Structural support	Inspection structural supports	Engineer
Swinging Stage	Assessment of supporting structure	Engineer
	Installation, erection, dismantling	Advanced Scaffolding Licence, AdvancedRigging Licence
	Operating swinging stage	Trained in safe work practices for swing stage including, daily inspections, loadcalculations & emergency procedures
	Inspection of cradle and suspension system	Advanced Scaffolding Licence, Advanced Rigging Licence
Traffic Control	Control traffic with a Stop/Slow bat	Traffic Control
	Set up and work with Traffic Control Guidance Schemes/Traffic Control Plans at a work site	Implement Traffic Control Plans
	Design new traffic management plans and TCGS/TCPs for road works, produce major upgrades ofstandard plans and/or inspect traffic control plans on road construction sites	Prepare a Work Zone Traffic ManagementPlan